

Engineering Specifications

**Loading Rack -
Deluge Foam - Water
Sprinkler Systems**

**Section 21 13 00 - Fire
Suppression Sprinkler Systems**

**Section 21 13 39 - Foam
Water Systems**

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

1. GENERAL

1.1 SYSTEM DESCRIPTION

This section describes the design and installation of the new and modified portions of the Fire Protection System and a new Foam Fire Protection System for the _____. The design flow rate shall be based on the information indicated on the drawings and this specification. The modified and new portions of the fire protection system shall be in accordance with NFPA 11, NFPA 13, the Owner's insurance carrier _____, and the local fire protection Authority Having Jurisdiction (AHJ). The Contractor is responsible for designing, furnishing, and installing all Fire Protection services, including but not limited to piping, wiring, equipment and devices as required for a complete, approved, and functioning system.

- 1.1.1 The Contractor shall provide a deluge foam-water fire sprinkler system for the _____ loading areas. Include all detectors, switches, alarms, wiring, and controls.
- 1.1.2 The Contractor shall hydraulically calculate and size all fire protection equipment, piping, and devices to ensure adequate flow to all system components. The Contractor shall verify the latest flow test data available by performing flow test on the water supply as required by NFPA to use as the basis of the hydraulic calculations. Tests to be representative of known high water use periods.

1.2 RELATED WORK [modify as required – see footer]

The drawings and general provisions of this contract including General and Supplementary conditions and all specification sections apply to work of this section. The _____ drawings and the _____ drawings describe the fire protection requirements. The Contractor shall also coordinate with other trades' drawings and contractors.

- A. Documents in Division 00 - Procurement Requirements apply to the work of this Section
- B. Sections in Division 01 - General Requirements apply to the work of this Section
- C. Sections in Division 21 – Fire Suppression
- D. Sections in Division 26 – Electrical
- E. Sections in Division 28 – Electronic Safety and Security

1.3 QUALITY ASSURANCE

A. Design Reliability:

The Designer for the fire protection systems shall meet one of the requirements below.

1. A registered Professional Engineer.
2. National Institute for Certification in Engineering Technologies (NICET) Level III in Water Based Systems Layout or Special Hazards Systems. Copies of the designer's certificate from NICET shall be submitted along with the drawings for approval.
3. The Contractor is responsible for the design and installation of the fire protection system (including required supports) in accordance with these specifications and the contract drawings. The Contractor shall coordinate with the other discipline drawings and respective Contractors to ensure a properly designed fire protection system for the building construction and occupancy classification.

B. Codes and Standards

The Contractor shall install the fire protection systems in accordance with the following Standards:

NFPA 11 Standard for Low, Medium, High-Expansion Foam

NFPA 13 Standard for the Installation of Sprinkler Systems

NFPA 70 National Electric Code

NFPA 72 National Fire Alarm Code

NFPA 101 Life Safety Code

National Electric Manufacturers Association (NEMA) Publication
Enclosures for Industrial Controls and Systems

Underwriters Laboratories, Inc. (UL) Publication – Fire Protection Equipment Directory

Factory Mutual (FM) Global requirements, if applicable to this project.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

C. Materials and Equipment

All equipment and devices shall be of a make and type listed by UL and/or approved by FM, or other nationally recognized testing laboratory for the specific purpose for which it is intended.

The Contractor shall provide fire protection products in accordance with UL standards; provide UL label on each product.

If applicable to this project, the Contractor shall design & install fire protection systems in accordance with FM requirements.

All products shall be listed and/or approved for fire protection service.

The fire protection systems shall be in conformance with all Federal, State, and Local requirements.

Inspect all materials to ensure that there is no damage and complies with product data submittals and drawings.

Contractor shall protect and store all system devices, equipment, piping, and foam concentrate per manufacturer's recommendations.

1.4 SUBMITTALS

Submit under provisions of Section 01 33 00 – Submittals.

Product Data: Submit manufacturer's product data, including type, model, and physical dimensions.

Complete literature and instructions provided by the manufacturer of all installed equipment and devices describing proper operation, maintenance, and safety requirements.

Piping layout drawings, electrical interface schematics, hydraulic calculations, and Contract Drawings shall be submitted to and approved by the owner's insurance carrier and the local fire protection authority prior to installation.

Contractor shall provide certification indicating that the system is installed in compliance with all applicable codes and standards.

Contractor shall provide verification that the appropriate acceptance tests have been conducted in accordance with the local fire protection authority and the applicable codes.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

Contractor shall provide project record drawings indicating location of all devices, piping, drains, etc. and include a sequence of operation.

1.5 DELUGE FOAM-WATER SPRINKLER SYSTEM DESIGN CRITERIA

[NOTE - NFPA 11 should be followed for most loading rack type protection scenarios that have available structure for installation of sprinkler piping.]

1.5.1 Provide a deluge, foam-water fire protection system for the _____ hazard areas as shown on Drawing _____.

1.5.2 The system shall include all accessories as are necessary for a complete and operational system. The foam-water system shall include but not be limited to the foam concentrate, foam bladder tank, foam proportioner, fire cross main, system control valves, deluge valve, control panels, associated wiring, sprinkler piping and sprinklers, nozzles and all accessories necessary for a complete and operational system.

1.5.3 The design of the foam-water system shall be by hydraulic calculations for uniform distribution of foam solution over the protected area and shall conform to the NFPA standards listed above and to the requirements specified herein.

1.5.4 Foam Concentrate

The foam concentrate shall be UL Listed or FM Approved for use on the flammable liquids present at the loading rack.

1.5.5 Distribution of Foam Solution

Distribution shall be essentially uniform throughout the area. Variation in discharge from individual sprinklers and nozzles shall be between 100 and 120 percent of the specified density.

1.5.6 Duration of Foam Discharge

System shall apply 3% foam solution over the sprinkler discharge area for a minimum of 10 minutes.

1.5.7 Sprinkler Discharge Area

Area shall be based on the entire loading rack area as defined by the drainage area or specified by the Authority Having Jurisdiction (AHJ).

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

1.5.8 Solution Application Density

The Contractor shall size the system to provide the specified density when the system is discharging the specified total maximum required flow. Application to horizontal surfaces below the sprinkler system shall be a minimum of [0.16 gpm/ft² for hydrocarbon fuels]. [_____ gpm/ft² for _____ which is a polar solvent fuel.]

[NOTE - Refer to the UL Listings for the published minimum application rates for Polar solvent fuels or contact CHEMGUARD for guidance].

The hydraulic calculations shall include an allowance for a 250 gpm (946 Lpm) outside water hose stream. This allowance shall not be included in the total foam concentrate required for the system.

[NOTE - If fueling system is bottom loading, under truck (ground sweep) nozzles may be recommended with a minimum of two CHEMGUARD TF nozzles per bay providing an additional 0.10 gpm/ft² (4.1 Lpm/m²) application density in addition to the coverage provided by the overhead foam-water sprinkler system.] Protection area is the calculated area under the truck/rail car.

1.5.9 Ground Sweep Nozzles

Ground sweep nozzles shall be installed for the dual axel area of the tractor(s) and trailer(s) for a total of two (2) nozzles per bay. The CHEMGUARD TF-____ aspirated discharge device shall be used.

1.5.10 Friction Losses

1.5.10.1 Calculated losses in foam solution piping shall be in accordance with the Hazen Williams formula with C value of 120 for galvanized steel pipe.

1.5.10.2 Calculated losses in foam concentrate piping shall be calculated based on foam manufacturer's published data showing maximum pressure differential at designed flow.

1.5.11 Location of Sprinklers and Nozzles

The quantity and location of the new sprinklers (and nozzles) serving the _____ areas shall be in accordance with Drawing _____.

Location and spacing of sprinklers shall conform to NFPA 11. The spacing of sprinklers on the branch lines shall be essentially uniform.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

1.5.12 Drainage

Each sprinkler riser shall be arranged so that it can be drained entirely through the main drain. The intent is to limit the number of auxiliary drains in the system due to trapped sections of piping. All piping in the system shall be pitched to a drain point accessible for the containment and collection of the foam solution.

- 1.6 The foam fire protection sprinkler system shall be automatically activated when one or more fire detectors activate.

1.6.1 Upon activation of any detector or manual pull the following shall immediately occur:

1.6.2 Activation of the deluge valve to send foam solution to the sprinkler heads.

1.6.3 An alarm shall be sent to the local fire alarm system.

1.6.4 Audible and visual alarms shall sound and light locally and on the foam fire protection system control panel.

2. PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS

- A. **CHEMGUARD (a brand of Johnson Controls)**, One Stanton St., Marinette, WI 54143, Tel: 715-735-7415, www.chemguard.com
 - B. **ANSUL® (a brand of Johnson Controls)**, One Stanton St., Marinette, WI 54143, Tel: 715-735-7415, (Toll Free) Tel: 800-862-6785, www.ansul.com
 - C. **TYCO (a brand of Johnson Controls)**, 1476 Elmwood Ave., Cranston, RI 02910, (Toll Free) Tel: 800-381-9312, www.tyco-fire.com
 - D. **Johnson Controls**, 5757 N. Green Bay Ave., Milwaukee, WI 53201, (Toll Free) Tel: 800-746-7539, www.johnsoncontrols.com
 - E. Proposed substitutions of other manufacturers not listed in these specifications must comply with provisions of Sections 00 43 25 and 01 25 00. Contractor must submit a Substitution Request Form. All substitutions must be pre-approved.
- 2.1.1 All equipment and components shall be new and the manufacturer's current model.
- 2.1.2 All equipment and components shall be installed in strict compliance with manufacturer's requirements.

Specifier Notes: This product guide specification is written according to the Construction Specifications Institute (CSI) 3-Part Format, including *MasterFormat*, *SectionFormat*, and *PageFormat*, as described in *The Project Resource Manual—CSI Manual of Practice, 2026 Edition*. This section must be carefully reviewed and edited by the Architect to meet the requirements of the project and local building code. Coordinate this section with other specification sections and the Drawings. Delete all Specifier Notes after editing this section.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

- 2.1.3 All equipment shall be attached to the structure and shall be held firmly in place. Fasteners and supports shall be adequate to support the required load per NFPA 13.
- 2.1.4 Sprinklers shall be standard pendent or upright type in all spaces and be listed for use with the foam concentrate.

2.2 Deluge Valves

Valves shall be operated by a detection and control system listed for the releasing service. The deluge valve shall be provided with electrical solenoids compatible with the voltage and current supplied by the control panel. If 6 in. valves are used in larger risers, provide smoothly tapered fittings. In addition to the automatic operation, arrange each valve for manual hydraulic release at the valve. Provide pressure gauges and the other appurtenances at the deluge valve. The Deluge Valve shall be TYCO Model DV-5A with associated trim, or approved equal. Where system pressures could exceed listed operating pressures the TYCO Pressure Regulating Model DV-5A Deluge Valve shall be used.

2.3 Foam Concentrate Injection

The foam proportioners shall be a modified venturi type designed to accurately proportion and control the mixing of pressurized foam concentrate into the water system. The proportioners shall have either NPT threaded (2 in. and 2 1/2 in. sizes) or "between flange" type (3 in., 4 in., 6 in. and 8 in. sizes) designed to fit between two 150 lb pipe flanges. Proportioners shall be sized for the specified flow rates and be UL listed or FM approved with the type of foam concentrate and bladder tanks being used in the system. A fixed metering orifice secured with a stainless steel retaining ring shall be sized according to the type and percentage of foam concentrate used.

The proportioners shall be a CHEMGUARD Part No. _____.

2.4 Hydraulic Concentrate Control Valve

The hydraulic concentrate control valve shall be a UL Listed and/or FM Approved assembly that is factory assembled and tested. It shall include a threaded bronze body ball valve with mounting kit for securely attaching the hydraulic actuator to ball valve. The ball valve shall be designed for a minimum 400 psi (27.6 bar) WOG. The valve shall be fitted with a stainless steel ball, stem, and packing nut. Valve seats shall be of glass reinforced TEFLON* material. The Stainless Steel Hydraulic Actuator must be approved by the manufacturer for using water as the medium to operate the actuator. The actuator shall have a position indicator and have the capability for

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

manual override. The actuator shall be designed to operate the valve with a minimum of 30 psi (2.1 bar) water pressure and shall contain no external moving parts which could cause fouling of adjacent equipment, injury to personnel, misalignment problems common to external linkage systems, or potential for disengagement caused by tampering.

The valves shall be a CHEMGUARD Part No. _____.

2.5 Foam Concentrate

Foam concentrate shall be UL Listed CHEMGUARD NFF-3H 3% Non-Fluorinated Foam Concentrate for hydrocarbon only hazards or UL Listed CHEMGUARD NFF-331 3% $\times$ 3% Non-Fluorinated Foam Concentrate for hazards that have both hydrocarbon and polar solvents. For Factory Mutual standard designs, the foam concentrate shall be CHEMGUARD NFF-332 3% $\times$ 3% Non-Fluorinated Foam for hydrocarbons and polar solvents.

2.6 Foam System Bladder Tanks

(Vertical) (Horizontal) cylindrical steel ASME coded pressure rated vessel with a UL Listed and/or FM Approved bladder shaped to conform to the inner pressure vessel configuration. Tank(s) shall be designed for a working pressure of 175 psi (12.1 bar) and hydrostatically tested to at least 255 psi (17.6 bar). The tank(s) interior shall be coated with a high-build epoxy sealer for additional corrosion resistance. The bladder tank(s) shall be UL Listed and/or FM Approved together with the type of concentrate and proportioner(s) being used in the system. The bladder tank(s) is to have a minimum _____ gal (_____) L capacity to provide sufficient foam concentrate for the time specified when the system is discharging foam solution at total discharge flow. The bladder tank shall be complete with all necessary outlets and supports such as a two welded saddles for horizontal bladder tanks or four welded legs for vertical bladder tanks. Associated trim on the bladder tank shall include bronze pipe and fittings, four bronze ball valves, minimum of 1 in., for concentrate and water vents and drains with secured nameplate depicting the valve name and operating position [, and a clear 1 in. PVC sight gauge]. The bladder tank(s), proportioner(s) and foam concentrate shall be the product of CHEMGUARD.

[NOTE - The Authority having jurisdiction shall advise on means of providing reserve supply of foam concentrate. NFPA 11 requires reserve supplies to be available for tank recharge within 24 hours. Many AHJ's may require use of reserve tank in equal capacity to main tank especially when owners cannot afford plant shut down while waiting on reserve foam delivery.]

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

2.7 Piping and Fittings

A. Foam Concentrate:

Piping for foam concentrate shall be brass, bronze, stainless steel or copper nickel in accordance with NFPA 11. Mechanical joints shall be UL Listed and/or FM Approved. Pipe thread sealant and PTFE tape shall be compatible with foam concentrate.

B. Above Grade:

Piping shall be carbon steel ASTM A795. Fittings shall be malleable iron, ASTM A197, ANSI B16.3 threaded, ASTM A34, ANSI 16.9, butt weld or grooved end mechanical joints. Pipe and fittings shall be in accordance with NFPA 13. Mechanical joints shall be UL Listed and/or FM Approved.

Piping for outdoor foam-water sprinkler systems shall be Schedule 40 galvanized steel and fittings shall have a hot dipped zinc-coated galvanized finish. Steel pipe welded and seamless, Type F, Grade A, ASTM A53; welded and seamless steel pipe for fire protection use, Type F, ASTM A795; electric resistance welded steel pipe, Grade A, ASTM A135. Pipe and fittings shall be in accordance with NFPA 11 and NFPA 13. Mechanical joints shall be UL Listed and/or FM Approved.

2.8 Discharge Devices

A. Standard Spray Sprinklers (Fusible Element removed in the field)

Standard coverage sprinklers are to be the basis for design unless noted otherwise on the plans. Sprinklers shall be cast brass or bronze finish. Sprinklers shall be UL Listed or FM Approved for the foam concentrate.

B. Foam-Water Sprinklers

Foam-Water Sprinklers shall be TYCO Model B-1 Air-Aspirating. The sprinkler shall be bronze finish, 1/2 in. NPT, K- Factor 3.0 with nominal orifice of 3/8 in.

2.9 Control System - General

All control systems shall be UL Listed and/or FM Approved with listed or approved compatible operating devices and shall be capable of the following functions:

Ground fault indication

Supervised alarm circuits

Supervised primary power circuit

Specifier Notes: This product guide specification is written according to the Construction Specifications Institute (CSI) 3-Part Format, including *MasterFormat*, *SectionFormat*, and *PageFormat*, as described in *The Project Resource Manual—CSI Manual of Practice, 2026 Edition*. This section must be carefully reviewed and edited by the Architect to meet the requirements of the project and local building code. Coordinate this section with other specification sections and the Drawings. Delete all Specifier Notes after editing this section.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

Remote Trouble Alarm

Battery standby

Front panel indicating lamps (LEDs) or (LCD) display

Key lock steel enclosure

2.10 Control Panel

The control panel shall be a UL Listed and/or FM Approved microprocessor-controlled control panel. Provide AUTOPULSE® Deluge Releasing Panel or approved equal.

The door shall provide a key lock and include a glass or other transparent opening for viewing of all indicators.

All interfaces and associated equipment are to be protected so they will not be affected by voltage surges or line transients.

The control panel shall receive one 120 Volt dedicated power feed.

The control panel shall be listed/compatible with all system components to include the solenoid.

2.11 Power Supply

Each power supply shall operate on 120 VAC, 60 Hz, and shall provide all necessary power for the foam fire protection system.

It shall provide a battery charger for 24 hours of standby.

It shall provide an earth detection circuit.

It shall provide optional meters to indicate battery voltage and charging current.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

2.12 Batteries

Batteries shall be 12 Volt.

Batteries shall have sufficient capacity to power each fire alarm system for not less than 24 hours in standby plus 5 minutes of alarm upon a normal AC power failure.

Batteries are to be completely maintenance free. No liquids are required. Fluid level checks, refilling, spills, and leakage are not acceptable.

2.13 Conduit

Conduit shall be in accordance with the National Electrical Code (NEC, local, and state requirements).

Conduit shall not exceed 40 percent of interior cross-sectional area where three or more cables are contained within a single conduit.

Cable must be separated from all open conductors of power or Class 1 circuits, and shall not be placed in any conduit, junction box, or raceway containing these conductors, as per NEC Article 760-136.

2.14 Wire

All fire alarm system wiring shall be new.

Wiring shall be in accordance with local, state, and national codes (for example, NEC Article 760). Number and size of conductors shall be as recommended by the fire alarm system manufacturer, but not less than 18 AWG for initiating device circuits, and 14 AWG for notification device circuits.

All wire and cable shall be listed and/or approved by a recognized testing agency for use with a protective signaling (fire alarm) system.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

3. EXECUTION

3.1 INSTALLATION

- 3.1.1 The Contractor shall coordinate with Owner any activity requiring an interface with existing plant services or other contractors to implement fire protection in the building.
- 3.1.2 The Contractor shall coordinate with the Owner to protect wet piping and system components from freezing in exterior or unheated spaces.
- 3.1.3 Installation shall be accomplished by the licensed contractor. Provide a qualified technician, experienced in the installation and operation of the type of system being installed to supervise the installation and testing of the system.
- 3.1.4 Installation of Piping: Accurately cut pipe to measurements established by the installer and install without springing or forcing. In any situation where bending of the pipe is required, a standard pipe-bending template must be utilized per NFPA 13.
- 3.1.5 Install the proportioner with the required minimum straight pipe lengths of the same nominal diameter before and after the proportioner. Must be 5 times before (upstream) and 2.5 times after (downstream).
- 3.1.6 Welding: Conform to the requirements and recommendations of NFPA 13.
- 3.1.7 Affix cutout disks, which are created by cutting holes in the walls of pipe for flow switches and non-threaded pipe connections to the respective waterflow switch or pipe connection near to the pipe from where they were cut.
- 3.1.8 Pipe hangers and supports shall comply with NFPA.
- 3.1.9 Sprinkler piping shall be installed so that the entire system may be drained.
- 3.1.10 Drains: Fire protection drains shall be piped to the exterior. If fire protection drains need to be piped to interior drains, the drains shall be of adequate size to readily carry the full flow from each drain under maximum pressure and be dedicated to fire protection use only. Install drips and drains where necessary and required by NFPA 13.
- 3.1.11 Test connections shall be provided as required by NFPA and the local fire marshal.
- 3.1.12 Supervisory Switches: Provide UL/FM supervisory switches for sprinkler control valves.
- 3.1.13 Waterflow Alarm Switches: Install UL/FM waterflow switches and adjacent valves in easily accessible locations. Securely attach identification signs to control valves, drain valves, and test valves. Locate hydraulic placard information signs at each sectional

Specifier Notes: This product guide specification is written according to the Construction Specifications Institute (CSI) 3-Part Format, including *MasterFormat*, *SectionFormat*, and *PageFormat*, as described in *The Project Resource Manual—CSI Manual of Practice, 2026 Edition*. This section must be carefully reviewed and edited by the Architect to meet the requirements of the project and local building code. Coordinate this section with other specification sections and the Drawings. Delete all Specifier Notes after editing this section.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

control valve where there is a zone water flow switch. Make sure identification placards for the proportioner and bladder tank are visible.

- 3.1.14 Mains, test connections, and other equipment shall be labeled per UL, FM and NFPA.
- 3.1.15 Provide the service of a competent factory-trained engineer or technician authorized by the manufacturer of the fire alarm equipment to technically supervise and participate during all of the adjustments and tests for the system. The factory representative shall demonstrate that the Foam Fire Protection Systems function properly in every respect.
- 3.1.16 Electrical and fire alarm installation shall be in accordance with the NEC, NFPA 72, local and state codes, as shown on the drawings, and as recommended by the major equipment manufacturer.
- 3.1.17 All conduit, junction boxes, conduit supports, and hangers shall be concealed in finished areas and may be exposed in unfinished areas.
- 3.1.18 All fire detection and alarm system devices, control panels, and remote annunciators shall be flush mounted when located in finished areas and may be surface mounted when located in unfinished areas.
- 3.1.19 All piping shall be closely coordinated with other trades (process piping, utility piping, HVAC, plumbing, electrical, general construction) to avoid interferences.
- 3.1.20 Penetrations through fire walls and floors shall be provided using appropriate methods to maintain their integrity as per Section 07 84 00 Fire Stopping.

3.2 INSPECTION AND TESTING

- 3.2.1 Preliminary Testing: Flush newly installed systems prior to performing hydrostatic tests in order to remove debris, ensuring piping is unobstructed. Hydrostatically test system, including the fire department connections, as specified in NFPA 13. Test and flush underground water line prior to performing these hydrostatic tests.
- 3.2.2 The Contractor shall hydrostatically test the entire Fire Protection system at 200 psi (13.8 bar) or where system design is in excess of 150 psi (10.3), test at a pressure 50 psi (3.4 bar) above system design pressure for 2 hours. Bladder tanks shall be isolated by manual valves and not be included in this test. For the hydrostatic test, the water pressure shall be increased in 50 psi (3.5 bar) increments with observations of the joint and gasket stability during each step increase. Increase pressure to the next increment only after joint and gasket stability has been demonstrated. After the required hydrostatic test pressure has been reached and maintained for one hour, the pressure shall be returned to zero while examining for leakage. The pressure shall be slowly increased again to the required hydrostatic test pressure and maintained for two hours

Specifier Notes: This product guide specification is written according to the Construction Specifications Institute (CSI) 3-Part Format, including *MasterFormat*, *SectionFormat*, and *PageFormat*, as described in *The Project Resource Manual—CSI Manual of Practice, 2026 Edition*. This section must be carefully reviewed and edited by the Architect to meet the requirements of the project and local building code. Coordinate this section with other specification sections and the Drawings. Delete all Specifier Notes after editing this section.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

while the leakage measurement is determined. All lines shall be relieved of pressure after completion of the test. In the event of repairs or additions, the affected piping shall be retested at the Contractor's expense. A Contractor's Material and Test Certificate shall be furnished by the Contractor and countersigned by the Owner's Representative. All shutoff valves shall be fully closed and opened under system pressure to ensure proper operation.

- 3.2.3 Foam Fire Protection Systems shall be tested only after all hydraulic testing and flushing is complete and all deficiencies found have been corrected to the satisfaction of the Owner.

- 3.2.4 Foam Discharge and Concentration Testing

Test each system riser at full design flow of foam solution from the individual riser or through temporary hose lines and nozzle to a test header for at least 60 seconds to collect a foam solution sample.

Test all foam-water hose line by full flow of foam solution for at least 60 seconds to collect a foam solution sample.

Provide measures to contain, collect and properly dispose of all foam-water discharge affluent. Disposal required to follow the applicable federal, state and local guidelines.

The manufacturer's representative shall test samples of foam solution taken from each system to ensure proper NFF concentration by means of conductivity or refractive index.

- 3.2.5 Flushing and Rinsing

After completion of tests, flush all piping carrying foam solution with fresh water.

Provide measures to contain, collect and properly dispose of all foam-water discharge affluent. Disposal required to follow the applicable federal, state and local guidelines.

- 3.2.6 Foam Concentrate Storage Tank

After acceptance of the system testing, bladder tanks shall be charged to the required tank capacity per manufacturer's recommendations.

- 3.2.7 Environmental Protection

Provide temporary measures to prevent foam solution from entering storm drains, sanitary sewers, drainage ditches, streams and water courses. Contain all foam solution on paved surfaces or specific containment area. Collect all discharge foam solution and dispose of it in an EPA approved manner. If a wastewater treatment facility is approved

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

for disposal, the wastewater treatment facility shall provide a secondary (biological) treatment.

- 3.2.8 Final Inspection and Testing: Subject system to tests in accordance with NFPA 13. Connection to the fire alarm system shall have been in service for at least ten days prior to the final inspection, with adjustments made to prevent false alarms. Furnish all instruments, labor and materials required for the tests and provide the services of the installation foreman or other competent representative of the installer to perform the tests. Correct deficiencies and retest system as necessary, prior to the final acceptance. Include the operation of all features of the systems under normal operations in test.

3.3 OWNER TRAINING

- 3.3.1 Instruct Owner's personnel in the proper operation, maintenance and testing of systems and equipment provided as part of this project. Include not less than ____ hours of instruction, using the operating and maintenance manuals and record drawings during this instruction. Demonstrate testing, startup and shutdown procedures for all equipment. All training to be during normal working hours. Video record all instructions and provide Owner with copy.

3.4 WARRANTY

3.4.1 Warranty Terms

The Contractor shall warranty all work performed and all material and equipment furnished under this contract to be free from defects and shall remain so for a period of at least one (1) year from the date of acceptance.

3.5 MAINTENANCE

3.5.1 Post Contract Maintenance

Complete maintenance and repair service for the Foam Fire Protection systems shall be available from a factory trained authorized representative of the manufacturer of the major equipment for a period of five (5) years after expiration of the warranty. The Contractor shall indicate this cost with his bid.

SECTION 21 13 00 – FIRE-SUPPRESSION SPRINKLER SYSTEMS
21 13 39 – FOAM WATER SYSTEMS
LOADING RACK - DELUGE FOAM-WATER SPRINKLER SYSTEMS

Note: The converted values in this document are provided for dimensional reference only and do not reflect an actual measurement.

CHEMGUARD, ANSUL®, TYCO, AUTOPULSE and the other product names listed in this material are marks and/or registered marks.
Unauthorized use is strictly prohibited.

*TEFLON is a trademark of The Chemours Company.

END OF SECTION

Specifier Notes: This product guide specification is written according to the Construction Specifications Institute (CSI) 3-Part Format, including *MasterFormat*, *SectionFormat*, and *PageFormat*, as described in *The Project Resource Manual—CSI Manual of Practice, 2026 Edition*. This section must be carefully reviewed and edited by the Architect to meet the requirements of the project and local building code. Coordinate this section with other specification sections and the Drawings. Delete all Specifier Notes after editing this section.